

**CLIENT:**

Jointline

CONTRACT:

Teeside Airport, Darlington

PROJECT DURATION:

December 2020 - January 2021

PROJECT VALUE:

£185,000

PROJECT OVERVIEW:

Taxiway Resurfacing

OUR INVOLVEMENT:

We planed key-in joints and then overlaid an area of just over 13500m² with SMA14. Whilst on site we also conducted some binder and surface patching works.

PROBLEMS FACED/SOLUTIONS OFFERED:

Our client needed someone who could get this work done cost effectively in a timely manner, which with the help of our supply chain we were able to do.

SUMMARY:

This job required a lot of preplanning to ensure all resources were aligned and understood what was expected of us. Good pre-start communication was key here.